

EMB Recording

Sr. No.	BoQ Items	Unit (UOM)	Total BoQ Qty.	Qty. as per Measurement	Upto Previous RA Qty.	Difference Qty.	Rate/ Unit
1	Earth work in filling in plinth	CUM	89			Invalid	
3	Fixing of glass panels or cleaning	Each	78			Invalid	
7	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement : 3 coarse sand) including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb shone shall be approved by Engineer-in-charge). UPPWD SOR-2020/16.69	CUM	2835			Invalid	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering All work upto plinth level. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) UPPWD SOR-2020/281 Kerb Stone	CUM	1799			Invalid	
2	Steel wooden truss	Each	90			Invalid	
4	Surfacing dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish, lead upto 50m and lift upto 1.5m UPPWD SOR-2020/2.28.1	SQM	4300187			Invalid	
5	Tractor trolley for disposal of grass. Lead upto 1/2 km.	Day	331			Invalid	
8	White washing with lime to give an even shade: New work (two or more coats) UPPWD/SOR-2020/13.37.1	SQM	1565394			Invalid	